



MOSSER ROAD HERITAGE TRAIL

Addendum #1

September 1, 2021

This Addendum includes answers to questions and clarifications to the contract bid documents for the Mosser Road Heritage Trail project bid set, which has a bid due date of September 8, 2021. The Invitation to Bid and all related documents can be accessed at www.garrettcollege.edu/purchasing.

Question 1: Are the drawings available in Auto CAD format?

Answer: The drawings in .dwg format have been posted to the website.

Question 2: Can you please provide the prevailing wage rates for the project?

Answer: Prevailing wage rates are not required for this project.

Question 3: Is the cost estimate worksheet to be turned in with the bid?

Answer: Yes, per the bid documents, the completed cost estimate worksheet (Attachment IV) should be included in the bid package.

Question 4: Where the trail crosses existing entrances, driveways, roads, etc., will the existing asphalt surface be removed and replaced per the trail pavement detail?

Answer: The existing asphalt at road crossings and entrances will not need to be removed and replaced. A smooth transition is all that is needed.



Question 5: On plan sheets PS-02, PS-03 and PS-04, what is the cross hatching from Sta 107+06 to Sta 121+05?

Answer: The cross hatching indicates a stormwater management credit area. There is nothing to construct. The disturbed area must be stabilized with seed and mulch.

Question 6: On plan sheet PS-04, what type of material is the 12" Culvert Pipe and end sections to be?

Answer: The 12" pipe is to be Corrugated Steel Pipe with end sections.

Question 7: Does the bridge need to be a Wheeler bridge?

Answer: No, the bridge specifications provided in the bid documents are two options. The contractor can use either of these or any supplier with a similar product.

--End of Addendum document--